



1	Fire Performance (FR-LSH PVC) Tests			Required Value	Observation Value
	a	Oxygen Index test @ 27 ± 2 Deg C	%	29 (Min.)	
	b.	Temperature Index	Deg C	250 (Min.)	
	c.	Flame Retardance Test on Single Cables	Visual	After the test, there should be no visible damages on the test specimen within 300 mm from its upper end. .	
	d	Flame Retardance Test on Bunched Cables	Visual	After burning has ceased, the cables should be wiped clean and the charred or affected portion should not have reached a height exceeding 2.5 m above the bottom edge of the burner.	
	e	Test for Light Transmission	%	70	
	f.	Test for pH and conductivity	Min	pH-4.3	
			$\mu\text{S/mm}$	10 (Max)	
	g	Test for Halogen acid gas evolution	%	0.5 (Max.)	
	h	Test for Smoke Density Rating	%	20 (Max.)	